







Problem definition

• Law

- Influence on construction process
- Effective and efficient
- What is needed?
- Important changes
 - Municipality does not longer check construction plans according to the Building Decree
 - · In stead of checks up front, now as-built statement

Research question

Is it possible with systems engineering (SE) and Building Information Modeling (BIM) to efficiently deliver an as-built statement which the independent quality inspector can present to the building permit holder under the Quality Assurance Act for construction (Wkb)?















| 1 - DRAFT | 2 - CONCEPT DESIGN | 3 - FINAL DESIGN | 4 - TECHNICAL DESIGN | 5 - CONSTRUCTION PLANNING | 6 - EXECUTION | 7 - MAINTENANCE |
|------------------|-----------------------|---------------------|-------------------------|------------------------------|---------------|-----------------|
| 1 PLANNING | | | | | | |
| 2 EQUIREMENTS | | | | | | |
| 3 RGANIZATION | | | | | | |
| 4 ROCUREMENT | | | | | | |
| 5 FINANCIAL | | | | | | |
| 6 KAM | | | | | | |

Step 2: Quality Checklists

| Related to the Building | N. | Phase | Building Decree article | IComponent I | What | How / Norm | Who | With what | Whe |
|---|----|-------|-------------------------------|---|---|---|-------------------------------|-------------------------------|-----|
| Decree | 5 | 4 | 2.2 /2.4 | Calculation lintels (supplier) | Requirement s: Do not collapse | NEN-EN 1990 & <u>1992</u> - <u>1996</u> | Constructive assessor | Check calculation | |
| | 6 | 5 | 5.3 | Thermal Itransmittance (U-window) | Requirement s: U _{we} : ≤1,65 (c.q. requirement EPC) W/m2K and Cf BRL 0801 | <u>NEN 1068</u> / KV + delivery receipt | Work planner (constructor) | <u>CP 303</u> | |
| | 7 | 5 | 5.3 | IManufacturin Ig window Iframes & Jdoors | <u>Cf BRL 0801</u> | KV + delivery receipt | Work planner (constructor) | <u>CP 303</u> + <u>304</u> | |

| ton 2. Control E | | | 4 | | | | | |
|---|----|--------------------------------|-----|-----------------------|---------|--|--|--|
| lep 3. Control r | | C | λ | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| VAN WIJNEN Meer dan bouwen | | CP303 Synthetic windows frames | | | | | | |
| Van Wijnen Deventer | | | | Projectnumber : | | | | |
| | | | | Date : | | | | |
| | | | | Clarification (action | Usedlad | | | |
| Component | Ар | pre | vai | Clarification/action | Handled | | | |
| General (phase 4) | Y | N | N/A | | | | | |
| KOMO-certificate present | | | | | | | | |
| Is the 'politiekeurmerk' applicable | | | | | | | | |
| | | | | | | | | |
| Construction planning (phase 5) | | | | | | | | |
| Preparing and monitoring drawing procedures | | | | | | | | |
| Sampling hinges and locks i.c.w. assembly by manufacturer | | | | | | | | |
| Protecting windows during execution phase | | | | | | | | |
| Planning en routing discussed | | | | | | | | |
| Making and checking windows frames | | | | | | | | |
| Dpc foil applied on windows frames | | | | | | | | |
| Measuring syntactic window frames | | | | | | | | |
| | | | | | | | | |
| Execution (phase 6) | | | | | | | | |
| Supply check windows frames | | | | | | | | |

| | QCL | SO | VO | DO | то | Construction | Execution |
|---|-----|----|----|----|----|--------------|---------------------|
| | 000 | | 2 | | | Planning | |
| 10 Quality Checklists | 100 | | 5 | 1 | | 1 | 5 |
| | 100 | | | 1 | | 1 | 6 |
| In total 110 | 104 | | | - | 1 | 2 | 3 |
| checks during | 200 | | | 3 | | 2 | 5 |
| | 300 | | | | | 6 | 4 |
| the building | 301 | | | 2 | 2 | 5 | 5 |
| process | 400 | | | | 1 | 9 | 5 (+2) ⁴ |
| | 500 | | | | | 7 | 15 |
| | 600 | | | | 3 | 2 | 10 |
| | TOT | 0 | 3 | 7 | 7 | 35 | 58 |

| | uit | | | | | | |
|--------------------------------|---|------------------------|---|---|---|--|---------------|
| | 1 - DRAFT | 2 - CONCEPT DESIGN | 3 - FINAL DESIGN | 4 - TECHNICAL DESIGN | 5 - CONSTRUCTION PLANNING | 6 - EXECUTION | 7 - MAINTENAN |
| 1 PLANNING | | | | | | | |
| 2 REQUIREMENT | | | | | | | |
| 3 ORGANIZATION | | | | | | | |
| 4 PROCUREMEN | | | | | | | |
| 5 FINANCIAL | | | | | | | |
| 6 KAM | VERIFICATION PROGRAM OF REQUIREMENTS | 3 CHECKS IN QCL 001 | 7 CHECKS IN GCL 100 102 200 300 | 7 CHECKS IN CCL 104 300 400 600 | 35 CHECKS IN GCL091 160 301 164 460 250 560 | 58 CHECKS IN OCL 100 102 104 200 300 301 400 500 600 AS-BUILT STATEMENT BO | |
| 7 RISKS AND OPPORTUNITIE | RISK ANALYSES AND MANAGEMENT MEASURES | | | | INSPECTION PLAN | | |
| 8 EXPERIEN <u>CES</u> | | | | | | | |









| Revit | | | |
|---|---|---|--|
| 3D drawing software Plugin | Image: control of the second secon | Image: | |



| _ | | | | | | | | | CP303 Synthetic wi | indov | /s fram | es | |
|---|-------|-------------------------------|--------------------------------------|--|----------------------------|-------------------------------|-------------------------------|------|--|-------|---------|----------------------------|---------|
| | Phase | Building Decree article | Component | What | How / Norm | Who | With what | When | Project | | | Projectnumber : Drafter | |
| | 4 | 2.2 /2.4 | Calculation lintels (supplier) | Requirements : Do not collapse | NEN-EN 1990 & 1992-1996 | Constructive assessor | Check calculation | | Location | | | Date : | |
| | 5 | 5.3 | Thermal transmittance | Requirements : U _{ave} : | NEN 1068/ KV + delivery | Work planner (constructor) | CP 303 | | Component | App | roval | Clarification/action | Handled |
| | | | (U-window) | ≤1,65 (c.q. requirement EPC) W/m2K | receipt | | Û | | General (phase 4) | Y N | N/A | | _ |
| | | | | and Cf BRI 0801 | | | | | KOMO-certificate present | | | | |
| | 5 | 5.3 | Manufacturin g window frames & | Cf BRL 0801 | KV + delivery receipt | Work planner (constructor) | <u>CP 303</u> + <u>304</u> | | Is the 'politiekeurmerk' applicable | | | | |
| | | | doors | | | | | | Construction planning (phase 5) | | | | |
| | | | | | | | | | Preparing and monitoring drawing procedures | | | | |
| | | | | | | | | | Sampling hinges and locks i.c.w. assembly by manufacturer | | | | |
| | | | | | | | | | Protecting windows during execution phase | | | | |
| | | | | | | | | | Planning en routing discussed | | | | |
| | | | | | | | | | Making and checking windows frames | | | | |
| | | | | | | | | | Dpc foil applied on windows frames | | | | |
| | | | | | | | | | Measuring syntactic window frames | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | Execution (phase 6) | | | | |

Conclusion

Systems Engineering in conjunction with a BIMsystem is a prerequisite to efficiently and effectively deliver the by the Wkb required as-built statement. The developed quality assurance system can theoretically be used without digital support. The costs (time spent) will be high with the risk that checks will be omitted, in which case the independent KB needs to spend extra time (costs).









